



Army Institute of Management
Plot No: III-B/11, Action Area III
New Town, Kolkata – 700 160
E- mail: saha.anindya@aim.ac.in
Website www.aim.ac.in

CORRIGENDUM – I:

Date: 12 Sep 2024

**0037/GEN/AIM/24- 25 DATED 06 SEP 2024 || REQUEST FOR PROPOSAL FOR SUPPLY,
INSTALLATION, TESTING & COMMISSIONING OF RO PLANT FOR BOY'S HOSTEL, ARMY
INSTITUTE OF MANAGEMENT, KOLKATA**

1. The following amendments may kindly be noted in the subject RFP:

FOR:

Point no 6: Last date of bids is 10:55 AM on 19 Sep 2024

READ:

Point no 6: Last date of bids is 10:55 AM on 19 Sep 2024

FOR:

Point no 7: Opening of Bids: Bids would be opened at 11:00 AM on 17 Sep 2024 in the Office of The Registrar/PO, Army Institute of Management, Rajarhat Campus. Bidders or their authorized representatives are welcome to be present on the day of tender opening.

READ:

Point no 7: Opening of Bids: Bids would be opened at 11:30 AM on 19 Sep 2024 in the Office of The Registrar/PO, Army Institute of Management, Rajarhat Campus. Bidders or their authorized representatives are welcome to be present on the day of tender opening.

FOR:

Point no 12,1: Recovery Rate: Minimum 50% recovery of input water

READ:

Point no 12,1: Recovery Rate: Minimum 70% recovery of input water

FOR:

Point no 12, 2:

- Pre-filtration Unit:
 - Iron removal filter
 - Activated Carbon Filter
 - Double Micron Filter
- RO Membrane
- Antiscalant Dosing System: To prevent scaling on membranes

ASB.

- Added Mineral system
- High-Pressure Pumps, Pressure Gauge, rota meters, flowmeter, SS SKID etc
- Control Panel
- Water Storage Tank: 1000-liter food-grade Stainless Steel tank for treated water storage

READ:

Point no 12, 2:

- 500 liter Raw water tank with proper raw water pump
- Pre-filtration Unit:
 - Iron removal filter
 - Activated Carbon Filter
 - Double Micron Filter
- RO Membrane
- Antiscalant Dosing System: To prevent scaling on membranes
- Added Mineral system
- High-Pressure Pumps, Pressure Gauge, rota meters, flowmeter, SS SKID etc
- Control Panel
- Water Storage Tank: 500-liter food-grade Stainless Steel tank for treated water storage

FOR:

Point no 12,4: Shading: RO plant to be shaded by tin sheet to protect from direct sunlight and rain

Read:

Point no 12,4: Shading: RO plant to be shaded by tin sheet to protect from direct sunlight and rain. IT should be 10ft x 15ft x 8ft. The shading should meet maintenance norms in future.

ADD:

Point no 12,8 : RO plant should have a cleaning system

Point no 12, 9: Consumable ITEM: Antiscalant (20kg), Added Minerals (50kg), Micron Cartridge (24 nos)

FOR:

Point no 13: Delivery & Installation period for the supply& installation of the items would be 20 working days from the effective date of Supply Order.

READ:

Point no 13: Delivery & Installation period for the supply& installation of the items would be 45 working days from the effective date of Supply Order.

2. REST NO CHANGE.

Note: Copy of the Corrigendum I dated 12 Sep 2024 with stamp & signature needs to be submitted along with other documents.

Yours faithfully,

AS
 (Dr. Anindya Saha)
 Presiding Officer

12/09/2024